

FCC Feasibility Study Mid-Term Status

FCC UK Meeting
29 November 2023

Michael Benedikt, CERN
on behalf of FCC collaboration & FCCIS DS team



FUTURE
CIRCULAR
COLLIDER
Innovation Study



Swiss Accelerator
Research and
Technology

<http://cern.ch/fcc>



Work supported by the **European Commission** under the **HORIZON 2020** projects **EuroCirCol**, grant agreement 654305; **EASITrain**, grant agreement no. 764879; **iFAST**, grant agreement 101004730, **FCCIS**, grant agreement 951754; **E-JADE**, contract no. 645479; **EAJADE**, contract number 101086276; and by the Swiss **CHART** program



European
Commission


Horizon 2020
European Union funding
for Research & Innovation

photo: J. Wenninger


FCC integrated program

comprehensive long-term program maximizing physics opportunities


- stage 1: FCC-ee (Z, W, H, $t\bar{t}$) as Higgs factory, electroweak & top factory at highest luminosities
- stage 2: FCC-hh (~100 TeV) as natural continuation at energy frontier, pp & AA collisions; e-h option
- highly synergetic and complementary programme boosting the physics reach of both colliders (e.g. model-independent measurements of the Higgs couplings at FCC-hh thanks to input from FCC-ee; and FCC-hh as “energy upgrade” of FCC-ee)
- common civil engineering and technical infrastructures, building on and reusing CERN’s existing infrastructure
- FCC integrated project allows the start of a new, major facility at CERN within a few years of the end of HL-LHC



2020 - 2046





2048 - 2063



2073 -

FCC integrated program - timeline

Note: FCC Conceptual Design Study started in 2014 leading to CDR in 2018



Realistic schedule takes into account:

- ☐ CERN Council approval timeline
- ☐ past experience in building colliders at CERN
- ☐ that HL-LHC will run until ~ 2041
- **ANY future collider at CERN cannot start physics operation before 2045-2048** (but construction will proceed in parallel to HL-LHC operation)

FCC Feasibility Study 2021-2025: main objectives

- ❑ Demonstration of the geological, technical, environmental and administrative feasibility of the tunnel and surface areas and optimisation of the placement and layout of the ring and related infrastructure.
- ❑ Pursuit, together with the Host States, of the preparatory administrative processes required for a potential project approval.
- ❑ Optimisation of the design of FCC-ee and FCC-hh colliders and their injector chains, supported by R&D to develop the needed key technologies.
- ❑ Elaboration of a sustainable operational model for the colliders and experiments in terms of human and financial resource needs, as well as environmental aspects and energy efficiency.
- ❑ Development of a consolidated cost estimate, as well as the funding and organisational models needed to enable the project's technical design completion, implementation and operation.
- ❑ Identification of substantial resources from outside CERN's Budget for the implementation of the first stage of a possible future project (tunnel and FCC-ee).
- ❑ Consolidation of the physics case and detector concepts and technologies for both colliders.

Objectives and deliverables presented to SPC and Council in June 2021:

https://indico.cern.ch/event/1038466/contributions/4386283/attachments/2259574/3834905/spc-e-1161-c-e-3588_FCC_MainDeliverables.pdf

Feasibility Study funded from CERN budget: 100 MCHF total over 5 years; in addition: ~ 20 MCHF/year for high-field magnet R&D
Additional funding from the European Commission and collaborating institutes (e.g., CHART collaboration with Switzerland)

FCC FS mid-term review: goal, deliverables, reviews

The goal of the FCC FS mid-term review is to assess the progress of the Study towards the final report.

Deliverables approved by the Council in September 2022:

https://indico.cern.ch/event/1197445/contributions/5034859/attachments/2510649/4315140/spc-e-1183-Rev2-c-e-3654-Rev2_FCC_Mid_Term_Review.pdf

Deliverables:

- D1 : Definition of the baselibe scenario
- D2 : Civil engineering
- D3 : Processes and implementation studies with the Host States
- D4 : Technical infrastructure
- D5 : FCC-ee accelerator
- D6: FCC-hh accelerator
- D7: Project cost and financial feasibility
- D8: Physics, experiments and detectors

← Many thanks to the Host States
for their strong support!

Documents:

- ☐ Mid-term report (all deliverables except D7)
- ☐ Executive Summary
- ☐ Updated cost assessment (D7)
- ☐ Funding model (D7)

Review process:

- ☐ Oct 2023: Scientific Advisory Ccommittee (scientific and technical aspects) and Cost Review Panel (ad hoc committee; cost and financial aspects)
- ☐ Nov 2023: SPC and FC
- ☐ 2 Feb 2024: Council



Many thanks to the SAC and CRP for their excellent work and the extremely useful reports!

Optimized placement and layout for feasibility study

Layout chosen out of ~ 100 initial variants, based on **geology** and **surface constraints** (land availability, access to roads, etc.), **environment**, (protected zones), **infrastructure** (water, electricity, transport), **machine performance** etc.

“Avoid-reduce -compensate” principle of EU and French regulations

Overall lowest-risk baseline: 90.7 km ring, 8 surface points,
Whole project now adapted to this placement





Meetings with municipalities concerned in France (31) and Switzerland (10)

PA – Ferney Voltaire (FR) – site experimental

PB – Présinge/Choulex (CH) – site technique

PD – Nangy (FR) – site experimental

PF – Roche sur Foron/Etaux (FR) – site technique

PG – Charvonnex/Groisy (FR) – site experimental

PH – Cercier (FR) – site technique

PJ – Vulbens/Dingy en Vuache (FR) site experimental


PL – Challex (FR) – site technique

Individual meeting

Individual meeting planned

Collective meeting




The support of the host states is greatly appreciated and essential for the study progress!





Connections to transport infrastructure


- Road accesses identified and documented for all 8 surface sites
- Four possible highway connections defined (materials transport)
- Total amount of new roads required < 4 km (at departmental road level)



Detailed road access scenarios
& highway access creation study
carried out by Cerema,
including regulatory
requirements in France

E.g. Valleiry Nord


FCC tunnel implementation



Tunnel implementation summary

- 91 km circumference
- 95% in molasse geology for minimising tunnel construction risks
- 8 surface sites with ~5 ha area each.

Status site investigations



- **Site investigations in areas with uncertain geological conditions:**
 - Optimisation of localisation of drilling locations ongoing with site visits since end 2022.
 - **Alignment with FR and CH on the process for obtaining autorisation procedures. Ongoing for start of drillings in Q2/2024.**
- **Contracts Status:**
 - Contract for engineering services and role of Engineer during works, active since July 2022
 - Site investigations tendering ongoing towards contract placement in December 2023 and mobilization from January 2024.




Sondage A89 (2007) incliné de 45° de 125 ml (surface plateforme estimée : 12 x 12 m soit environ 150 m²)



Drilling works on the lake

- **Technical Site (PB)**




CE surface progress



**Generic study of experiment
site and technical site by
FNAL**

Examples of Fermilab Deliverables

- bills of quantities extracted from FNAL designs
- basis for cost estimate by consultant with experience on industrial constructions in CH-FR area.






Preparatory phase planning - authorisations and CE

To start the excavation of the first shafts in 2033, a significant amount of preparatory work is required. An initial consideration of these preparatory works including scheduling and resource aspects has been made:

| 2025-2026 | Permits and authorization for complementary site investigations |
|---------------|--|
| | Tendering for environmental impact and authorisation processes contract, tendering for subsurface investigations |
| 2027-28 | Complementary subsurface investigations |
| | Tendering for CE consultants, environmental impact studies, public concertation |
| 2028 | Project approval |
| | Award of CE consultant contracts |
| 2029-30 | Tender design |
| | Preparing calls for tenders for CE construction, |
| | Project authorisations in France and Switzerland obtained |
| 2031 mid 2032 | Construction design, Tendering for construction |
| mid 2032 | Award of CE construction contracts |
| | Preparation of site (road access, electricity, water...) |
| 2033 | Ground breaking |

Connections to electrical grid infrastructure


| Updated FCC-ee energy consumption | Z | W | H | TT |
|---|-------------|-------------|-------------|-------------|
| Beam energy (GeV) | 45.6 | 80 | 120 | 182.5 |
| Max. Power during beam operation (MW) | 222 | 247 | 273 | 357 |
| Average power / year (MW) | 122 | 138 | 152 | 202 |
| Total FCC-ee yearly consumption (TWh) | 1.07 | 1.2 | 1.33 | 1.77 |
| Yearly consumption CERN & SPS (TWh) | 0.70 | 0.70 | 0.70 | 0.70 |
| Total yearly consumpt. CERN & SPS & FCC-ee (TWh) | 1.77 | 1.90 | 2.03 | 2.47 |





The loads could be distributed on three main sub-stations (optimally connected to existing regional HV grid):

- **Point D with a new sub-station** covering PB – PD – PF – PG
- **Point H with a new dedicated sub-station** for collider RF
- **Point A with existing CERN station** covering PB – PL – PJ
- **Connection concept was studied and confirmed by RTE (French electrical grid operator) → requested loads have no significant impact on grid**
- **Powering concept and power rating of the three sub-stations compatible with FCC-hh**
- **R&D efforts aiming at further reduction of the energy consumption of FCC-ee and FCC-hh**

PDL1, 69MW



Cooling water supply concept



- Potential sources of cooling water Geneva lake (PA), Rhone (PJ) and Arve (PD).
- Existing line with lake water provided by SIG to CERN LHC P8 (LHCb) sufficient for FCC-ee.
- Pipework in the tunnel will connect the remaining points to points PA, PD and PJ.
- Main cooling towers placed at experiment points (PA, PD, PG, PJ), and RF sites (PL, PH).

FCC-ee: main machine parameters

| Parameter | Z | WW | H (ZH) | ttbar |
|--|--------------|-------------|-------------|-------------|
| beam energy [GeV] | 45.6 | 80 | 120 | 182.5 |
| beam current [mA] | 1270 | 137 | 26.7 | 4.9 |
| number bunches/beam | 11200 | 1780 | 440 | 60 |
| bunch intensity [10^{11}] | 2.14 | 1.45 | 1.15 | 1.55 |
| SR energy loss / turn [GeV] | 0.0394 | 0.374 | 1.89 | 10.4 |
| total RF voltage 400/800 MHz [GV] | 0.120/0 | 1.0/0 | 2.1/0 | 2.1/9.4 |
| long. damping time [turns] | 1158 | 215 | 64 | 18 |
| horizontal beta* [m] | 0.11 | 0.2 | 0.24 | 1.0 |
| vertical beta* [mm] | 0.7 | 1.0 | 1.0 | 1.6 |
| horizontal geometric emittance [nm] | 0.71 | 2.17 | 0.71 | 1.59 |
| vertical geom. emittance [pm] | 1.9 | 2.2 | 1.4 | 1.6 |
| horizontal rms IP spot size [μm] | 9 | 21 | 13 | 40 |
| vertical rms IP spot size [nm] | 36 | 47 | 40 | 51 |
| beam-beam parameter ξ_x / ξ_y | 0.002/0.0973 | 0.013/0.128 | 0.010/0.088 | 0.073/0.134 |
| rms bunch length with SR / BS [mm] | 5.6 / 15.5 | 3.5 / 5.4 | 3.4 / 4.7 | 1.8 / 2.2 |
| luminosity per IP [$10^{34} \text{ cm}^{-2}\text{s}^{-1}$] | 140 | 20 | 5.0 | 1.25 |
| total integrated luminosity / IP / year [ab^{-1}/yr] | 17 | 2.4 | 0.6 | 0.15 |
| beam lifetime rad Bhabha + BS [min] | 15 | 12 | 12 | 11 |

currently assessing
technical feasibility
of changing operation
sequences
(e.g. starting at ZH energy)

4 years
 5×10^{12} Z
LEP $\times 10^5$

2 years
 $> 10^8$ WW
LEP $\times 10^4$

3 years
 2×10^6 H





5 years
 2×10^6 tt pairs

- x 10-50 improvements on all EW observables
- up to x 10 improvement on Higgs coupling (model-indep.) measurements over HL-LHC
- x10 Belle II statistics for b, c, τ
- indirect discovery potential up to ~ 70 TeV
- direct discovery potential for feebly-interacting particles over 5-100 GeV mass range

Up to 4 interaction points \rightarrow robustness,
statistics, possibility of specialised detectors
to maximise physics output


Operation sequences for FCC-ee

O. Brunner, F. Peauger






FCC-ee injector layout & implementation



implementation study on Preveessin site



FCC-hh layout, optics work, geom. integration

| parameter | FCC-hh | HL-LHC | LHC |
|--|-------------|----------|------|
| collision energy cms [TeV] | 81 - 115 | 14 | |
| dipole field [T] | 14 - 20 | 8.33 | |
| circumference [km] | 90.7 | 26.7 | |
| arc length [km] | 76.9 | 22.5 | |
| beam current [A] | 0.5 | 1.1 | 0.58 |
| bunch intensity [10^{11}] | 1 | 2.2 | 1.15 |
| bunch spacing [ns] | 25 | 25 | |
| synchr. rad. power / ring [kW] | 1020 - 4250 | 7.3 | 3.6 |
| SR power / length [W/m/ap.] | 13 - 54 | 0.33 | 0.17 |
| long. emit. damping time [h] | 0.77 – 0.26 | 12.9 | |
| peak luminosity [$10^{34} \text{ cm}^{-2}\text{s}^{-1}$] | ~30 | 5 (lev.) | 1 |
| events/bunch crossing | ~1000 | 132 | 27 |
| stored energy/beam [GJ] | 6.1 - 8.9 | 0.7 | 0.36 |

With FCC-hh after FCC-ee:
significantly
more time for high-field
magnet R&D
aiming at highest possible
energies

Formidable challenges:

- ❑ high-field superconducting magnets: 14 - 20 T
- ❑ power load in arcs from synchrotron radiation: 4 MW → cryogenics, vacuum
- ❑ stored beam energy: ~ 9 GJ → machine protection
- ❑ pile-up in the detectors: ~1000 events/xing
- ❑ energy consumption: 4 TWh/year → R&D on cryo, HTS, beam current, ...


Formidable physics reach, including:

- ❑ Direct discovery potential up to ~ 40 TeV
- ❑ Measurement of Higgs self to ~ 5% and ttH to ~ 1%
- ❑ High-precision and model-indep (with FCC-ee input)
measurements of rare Higgs decays ($\gamma\gamma$, $Z\gamma$, $\mu\mu$)
- ❑ Final word about WIMP dark matter

high-field magnets for FCC-hh: Nb₃Sn & HTS R&D

PSI Nb₃Sn CCT «CD1» main test carried out in 2022/23

PSI CCT CD1 quenches



It trained **A LOT**. It reached **100% of maximum field at 4.5 K**. No conductor degradation occurred from handling, assembly, powering, or thermal cycling.

Stress-management works, CD1 is a robust magnet.


B. Auchmann

Next: FCC-hh SM-CC Demonstrator

Goal: demonstrate robust and cost-efficient Nb₃Sn technology for next ESPPU.

Novel concept: Stress-managed and asymmetric common coils.

Stainless steel shell
Iron yoke
Coil collar
Former
Non-magnetic poles
Nb₃Sn conductor




B₀ target of 14 T, at T_{op}: 4.2 K
Eng margin of 10%
B₀ short sample @ 1.9 K: 16 T


D. Araujo

Rough estimates

Bottom line: HTS technology must catch over the coming 10 years in TRL to LTS



HTS Innovation Funnel for HFM



Status of FCC global collaboration

increasing international collaboration as a prerequisite for success

150

Institutes

32

Companies

34

Countries



FCC Feasibility Study: Aim is to increase further the collaboration, on all aspects, in particular, on Accelerator and Particle/Experiments/Detectors (PED).



The first half of the FCC Feasibility Study is being completed with the mid-term review

- 20 – 22 November 2023: SPC and FC review meetings on mid-term review
- 2 February 2024: CERN Council meeting on mid-term review


Focus 2021 - 2023:

- identifying best placement & layout and adapting entire project to new placement
- this provided the input for the mid-term review documentation and cost estimate update

Fruitful collaboration between scientific & technical actors, in close cooperation with the host state services concerned, at departmental/cantonal and local level. Direct exchange in place with communes concerned by surface sites. Environmental studies ongoing.

Focus 2024 - 2025:

- Subsurface investigations, further optimization of implementation, surface sites, synergies, etc.
- Full design iteration in view of technical and cost optimisation of entire project.



home.cern